

TX 4017

CONSTRUCTION TELEHANDLERS



Key Features

- ✓ 4 Equal Wheels
- ✓ 4-Wheel Steering
- ✓ 3 Steering Modes
- ✓ Torque Converter Transmission
- ✓ Perkins 94hp Engine

Key Specifications

- ✓ 17.4m Lifting Height
- ✓ 4 Ton Capacity
- ✓ 13.48m Reach
- ✓ 38mm Ground Clearance

SPECIFICATIONS

		METRIC
Capacities	Max. capacity	4000 kg
	Max. lifting height	17.40 m
	Max. outreach	13.48 m
Weight and dimensions	Overall length to carriage	6.20 m
	Overall width	2.38 m
	Overall height	2.59 m
	Wheelbase	2.90 m
	Ground clearance	0.38 m
	Overall cab width	0.85 m
	External turning radius (over tyres)	4.05 m
	Unladen weight (with forks)	11275 kg
	Overall weight	11235 kg
	Forks length / width / section	1200 mm x 125 mm x 50 mm
Performances	Lifting	13.60 s
	Lowering	9.40 s
	Extension	25 s
	Retraction	14.10 s
	Crowd	4.10 s
	Dump	3.20 s
Engine	Engine brand	Perkins
	Engine norm	Stage IIIA
	Engine model	1104D-44T EPA
	Number of cylinders / Capacity of cylinders	4 - 4.40 l
	I.C. Engine power rating - Power	92 Hp / 70 kW
Max. torque	392 Nm	
Transmission	Transmission type	Torque converter with manual transmission
	Number of gears (forward / reverse)	4 / 4
	Max. travel speed	28 km/h
	Max. travel speed (may vary according to applicable regulations)	28 km/h
	Parking brake	Manual
	Service brake	Oil-immersed multi-discs braking on front & rear axles
Hydraulics	Hydraulic pump type	Gear pump
	Hydraulic flow / Pressure	96.70 l/min-250 bar
Tank capacities	Hydraulic oil	120 l
	Fuel tank	78.50 l
Noise and vibration	Noise at driving position (LpA)	92 dB
	Noise to environment (LwA)	110 dB
Miscellaneous	Steering wheels (front / rear)	2 / 2
	Drive wheels (front / rear)	2 / 2
	Safety	Standard EN 15000
	Controls	Monolever



STANDARD FEATURES

- ROPS/FOPS Level II Overhead Guard
- Battery cut-off
- Cab Enclosure
- Cyclonic air prefilter

OPTIONAL FEATURES

- Attachment hydraulic line
- Windscreen protection grid
- Aggravating_movements_cut_off_EN_15000
- Manual air conditioning
- Work Lights - Front and Rear
- Heating

Manitou Group reminds users to read and understand the operator's manual before operating any equipment. Also, make sure all safety devices and shields are in place and functioning properly. Manitou Group reserves the right to add improvements or make changes in specifications at any time without notice or obligation.



One Gehl Way, West Bend, WI 53095
Phone: (262) 334-9461



GEHL COMPACT EQUIPMENT